# STRUCTURE LOCATION

# ARTHUR KEY PLAN

# LIST OF DRAWINGS

00 - COVERSHEET

01 - EROSION & SEDIMENT CONTROL PLAN & DEWATERING PLAN

02 - PLAN & PROFILE

# TOWNSHIP OF WELLINGTON NORTH





CONTRACT FOR

REPLACEMENT OF WELLS STREET CULVERT ARTHUR

CONTRACT No. RFT 2024-012

ISSUED FOR APPROVALS - JULY 2024
ISSUED FOR TENDER - AUGUST 2024
ISSUED FOR CONSTRUCTION - -





- 5. EXCAVATE AS REQUIRED IN ORDER TO INSTALL GRANULAR BEDDING, PROPOSED CONCRETE BOX CULVERT, AND WATERPROOFING.
- 6. PLACE GRANULAR SUBSTRATE AND GRADED RIVERSTONE AS REQUIRED TO RESTORE WATERCOURSE STREAMBED WITHIN WORK AREA. 7. PLACE BACKFILL AROUND PROPOSED CONCRETE BOX CULVERT AS REQUIRED TO FACILITATE REMOVAL OF COFFERDAMS. PLACE ROCK
- 8. REMOVE COFFERDAMS. 9. COMPLETE REMAINING WORKS.
- 10. RESTORE THE SITE TO EXISTING OR BETTER CONDITION, COMPLETE WITH THE INSTALLATION AND MAINTENANCE OF SILT FENCE AND STRAW BALE CHECK DAMS UNTIL VEGETATION HAS REESTABLISHED.

THIS DEWATERING PLAN IS CONCEPTUAL ONLY; THE CONTRACTOR SHALL SUBMIT A DEWATERING PLAN TO THE CONTRACT ADMINISTRATOR AND GRCA FOR APPROVAL PRIOR TO CONSTRUCTION.

- 3. EXISTING FILL AND SURFICIAL ORGANIC MATERIALS SHALL BE SUBEXCAVATED TO NATIVE SOIL AND REPLACED WITH GRANULAR B TYPE III.
- 4. NO GRANULAR BEDDING SHALL BE PLACED UNTIL THE DEPTH OF EXCAVATION AND THE SUBGRADE HAVE BEEN APPROVED BY THE CONTRACT ADMINISTRATOR'S GEOTECHNICAL ENGINEER.

## EROSION CONTROL — CULVERT REPLACEMENT:

- 1. ALL WORK SHALL BE DONE IN THE DRY. WORK TO BE COMPLETED ONLY DURING FORECASTED PERIOD OF DRY WEATHER.
- 2. IN-WATER WORKS SHALL TAKE PLACE BETWEEN JULY 1 AND SEPTEMBER 15 UNLESS OTHERWISE APPROVED BY ALL APPLICABLE REGULATORY AUTHORITES.
- 3. DEWATERING OF THE SITE SHALL BE ACHIEVED BY THE INSTALLATION OF COFFERDAMS TO ISOLATE THE WORKING AREA, AND THE PLACEMENT OF FLOW DIVERSION AND/OR CONVENTIONAL SUMP PUMPS WHERE REQUIRED. A MINIMUM 2-WEEKS PRIOR TO COMMENCING THE PROPOSED WORKS, THE CONTRACTOR SHALL SUBMIT A DEWATERING PLAN, DETAILING SPECIFIC METHODOLOGY, TO BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR AND APPLICABLE CONSERTVATION AUTHORITY. ANY DEVIATION FROM PLAN IS TO BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR AND APPLICABLE CONSERVATION AUTHORITY.
- 4. PUMPS SHALL BE DISCHARGED INTO A 'FILTER BAG' OR 'SEDIMENT BOX' TO PREVENT DELETERIOUS MATERIAL FROM ENTERING THE WATERCOURSE. THE CONTRACTOR SHALL PROVIDE A STAND-BY PUMP CAPABLE OF DEWATERING FOR USE INCASE THE FLOW IN THE WATERCOURSE INCREASES BEYOND THE CAPACITY OF THE PUMPING SYSTEM. PUMPS ARE TO BE EQUIPPED WITH FISH SCREENS WITH OPENING NO LARGER THAN 2.54mm.
- 5. COFFERDAMS AND TEMPORARY FLOW PASSAGE SHALL BE DESIGNED BY THE CONTRACTOR AND SUBMITTED TO THE CONTRACT ADMINISTRATOR FOR REVIEW AND APPROVAL, A MINIMUM OF 2-WEEKS PRIOR TO COMMENCING THE PROPOSED WORKS. ANY DEVIATION FROM PLAN IS TO BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ALL DISTURBED AREAS INCLUDING BANKS ABOVE WATER LEVEL, WHICH ARE NOT DESIGNATED FOR ROCK PROTECTION, SHALL BE REGRADED, TOPSOILED AND SEEDED AS SOON AS POSSIBLE. ALL DISTURBED AREAS WITH SLOPES OF 3:1 OR GREATER SHALL INCLUDE A BIODEGRADABLE EROSION CONTROL BLANKET.

7. ALL EROSION CONTROL MEASURES (SILT FENCE, SEDIMENT CURTAIN ETC.) SHALL BE CHECKED DAILY DURING ON—SITE WORK AND BE MAINTAINED IN GOOD STATE SO THAT

- THEY ARE FUNCTIONING PROPERLY. 8. NO MACHINERY SHALL CROSS THE WATERCOURSE AT ANY TIME. ANY MACHINERY THAT IS REQUIRED ON THE OTHER SIDE OF THE WATERCOURSE SHALL BE HAULED BY FLOAT OR DRIVEN AROUND ON THE ROADS. MACHINERY, VEHICLES, EQUIPMENT, PUMPS, ETC., SHALL NOT BE REFUELED WITHIN 30 METRES OF THE WATERCOURSE.
- MACHINERY SHALL NOT BE CLEANED WITHIN 30 METRES OF THE WATERCOURSE.
- 9. ALL WASTE MATERIAL FROM CONSTRUCTION SHALL BE STORED A MINIMUM OF 30 METRES AWAY FROM AND ABOVE THE HIGH WATERMARK. THE CONTRACTOR SHALL INSTALL SILT FENCE AROUND ANY STOCK-PILED MATERIAL, AS REQUIRED, TO PREVENT ANY MATERIAL FROM ENTERING THE WATERCOURSE.
- 10. FOR TYPICAL CHECK DAMS REFER TO OPSD 219.180 AND OPSD 219.211.
- 11. FOR SILT FENCE DETAIL REFER TO OPSD 219.130.
- 12. SEED MIX TO BE 'RURAL ONTARIO ROADSIDE NATIVE SEED MIXTURE 8145'.

- 1. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO COMMENCEMENT OF WORKS AND MAINTAINED DURING THE
- WORK PHASE, TO PREVENT THE ENTRY OF SEDIMENT INTO THE WATER OR THE MOVEMENT OF RE-SUSPENDED SEDIMENT. 2. ALL DISTURBED WORK AREAS SHALL BE STABALIZED AND RE-VEGETATED AS REQUIRED UPON THE COMPLETION OF WORK AND RESTORED
- 3. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE LEFT IN PLACE UNTIL ALL DISTURBED AREAS HAVE BEEN STABALIZED AND RE-VEGETATED.
- 4. EXISTING STREAM FLOWS SHALL BE MAINTAINED DOWNSTREAM OF THE DE-WATERED WORK AREA WITHOUT INTERRUPTION, DURING ALL
- STAGES OF WORK. THERE SHOULD BE NO INCREASE IN UPSTREAM WATER LEVELS OF THE DE-WATERED WORK AREA.
- 5. SILT OR DEBRIS THAT HAS ACCUMULATED AROUND THE TEMPORARY COFFERDAMS SHALL BE REMOVED PRIOR TO THEIR REMOVAL.
- 6. ENSURE THAT MACHINERY ARRIVES ON SITE IN A CLEAN, WASHED CONDITION AND IS MAINTAINED FREE OF FLUID LEAKS. WASH, REFUEL AND SERVICE MACHINERY AND STORE FUEL AND OTHER MATERIAL FOR THE MACHINERY AWAY FROM THE WATERCOURSE TO PREVENT ANY DELETERIOUS SUBSTANCE FROM ENTERING THE WATERCOURSE.
- 8. KEEP AN EMERGENCY SPILL KIT ON-SITE IN CASE OF FLUID LEAKS OR SPILLS FROM MACHINERY.

DRAWN BY:

CHECKED BY:

APRIL 2024

9. CONCRETE LEACHATE IS ALKALINE AND HIGHLY TOXIC TO FISH AND AQUATIC LIFE AND MEASURES MUST BE TAKEN TO PREVENT ANY INCIDENCE OF CONCRETE OR CONCRETE LEACHATE FROM ENTERING THE WATERCOURSE.

ALL EXISTING ELEVATIONS & DIMENSIONS TO BE CONFIRMED ON SITE. THE LOCATION OF UTILITIES IS APPROXIMATE ONLY AND SHOULD BE, DETERMINED BY CONSULTING THE MUNICIPAL AUTHORITIES AND UTILITY COMPANIES CONCERNED. THE CONTRACTOR SHALL PROVE THE LOCATION OF UTILITIES AND SHALL BE RESPONSIBLE FOR ADEQUATE PROTECTION AGAINST DAMAGE.

AUG 2024 | ISSUED FOR TENDER I | JULY 2024 | ISSUED FOR GRCA APPROVAL No DATE REVISION

CULVERT REPLACEMENT WELLS ST. EAST (ARTHUR)

TOWNSHIP OF WELLINGTON NORTH 7490 SIDEROAD 7 WEST KENILWORTH, ONTARIO NOG 2E0

EROSION & SEDIMENT CONTROL PLAN & DEWATERING PLAN

CONTRACT No. 5991-24 M5991 PROJECT No. APPROVED BY: P.F.Z.

**ENGINEERING** 

H: 1: 250 H: 1: 500 UNLESS OTHERWISE SHOWN

DRAWING NUMBER

01

